

## **ADDENDUM No. 1**

### **Montello Street at Route 58 Re-alignment Project Carver, Massachusetts**

**July 27, 2021**

The following Addendum No. 1 is hereby issued to the Bid Documents entitled, “Montello Street at Route 58 Re-alignment,” dated July 21, 2021.

All prospective bidders shall be aware of all clarifications and revisions as follows and should note such within the bidding documents at the time of bidding.

The following questions have been asked by a prospective bidder. Responses are provided below each question.

1. Q: Can you please define the areas of reclaim (item 403.) for the base bid.

A: All proposed full depth pavement areas that are located within the footprint of existing roadway pavement are to be reclaimed. For the base bid, this applies to the proposed full depth pavement on Main Street from STA 12+25± LT to STA 16+50± LT and the proposed full depth pavement on Montello Street from STA 107+75± to STA 112+60±. See the Pavement Notes next to the Typical Sections on plan sheet 7.

2. Q: Item # 450.32, aside Main Street, where is it being used.

A: Item 450.32 – Superpave Intermediate Course – 19.0 (SIC – 19.0) is to be used in all proposed full depth pavement areas. This item is being used in lieu of typical base course pavement. See the Pavement Notes next to the Typical Sections on plan sheet 7.

3. Q: Item # 904, where is it being used.

A: Item 904. – 4000 PSI, 3/4 Inch, 610 Cement Concrete has been placed in the bid as a say quantity in case it is needed during the project’s construction.